



POWERED BY SIFI NETWORKS

NOTICE OF CONSTRUCTION

A CITYWIDE FIBER OPTIC NETWORK IS BEING INSTALLED.



SIFI NETWORKS WILL BE RESPONSIBLE FOR RESTORING THE AREAS IMPACTED BY THEIR CONSTRUCTION IN THE GREENBELT. IF YOU HAVE SPRINKLER SYSTEMS OR INVISIBLE DOG LINES PLEASE MARK THESE OUT.



PLEASE TURN OVER FOR DETAILED INFORMATION ON OUR CONSTRUCTION PHASES.

If you have any questions regarding the construction of the FiberCity® project, contact us:

+1 (888) 766 9475

info@sifinetworks.com

FARMINGTONAREAFIBERCITY.COM

FIBERCITY® and SIFI® are registered trademarks of Sifi Networks America, Ltd. Retail services are provided by unaffiliated third-party internet service providers. © 2023 Sifi Networks America. All Rights Reserved.



POWERED BY SIFI NETWORKS

IMPORTANT INFORMATION

Prior to any work commencing, you will see colored flags placed by your local utility providers, identifying their infrastructure to ensure we work safely and avoid existing utilities.

We will be utilizing different deployment methods throughout the multiple phases of the build in your neighborhood, which typically takes up to 90 days to complete, depending on weather conditions.

Phase 1: Our team will be marking out areas on your street with water based white or pink paint prior to installing ground level chambers (24" x 36") to support the next phase of construction. Typically taking 5-10 days.

Phase 2: Typically starting 14-21 days after the completion of phase 1. Using specialized machines, we will bore under driveways, trees and across roads. You may see black pipe sticking out of the ground, the pipes will be marked and then buried during the next phase of construction.

Phase 3: You will receive a second notice prior to this phase starting, typically 45-60 days after phase 2. We will create a trench in the greenbelt approximately 4 inches wide and 8-12 inches deep where our infrastructure will be placed and the soil backfilled.

Phase 4: Depending on weather conditions, the restoration crew will return to complete the remediation which includes dirt grading, placement of grass seed, and bio-degradable straw matting, this indicates construction is complete and you may remove locate flags.

We encourage you to water the area covered by the straw matting which may be removed once the grass has grown to about 3-4 inches. It could take up to 60 days for the grass to grow.

Please note that winter restoration may be delayed further due to poor weather conditions.

Española



हिन्दी



عربي



FIND OUT WHO YOUR INTERNET SERVICE PROVIDERS ARE AT
FARMINGTONAREAFIBERCITY.COM